

ROLAIR[®] COMPRESSORS

S Y S T E M S

606 South Lake Street > P.O.Box 346 > Hustisford, WI 53034-0346 > **920.349.3281** > fax 920.349.3691 > www.rolair.com

Super Quiet!
Only 4.6 Amps



Model AB5

Direct Drive - Oilless

- **1/2 HP** 1725 RPM, Manual Reset
- **.7 CFM** Delivered at **90 PSI**, **1.4** Displaced

**Runs Approximately*
• 1 Trim/Finish Gun

Low Speed
Low Noise



Model VT20TB

Direct Drive - Splash Lubricated

- **2 HP** 1700 RPM, Manual Reset
- **4.2 CFM** Delivered at **90 PSI**, **5.5** Displaced

**Runs Approximately*
• 1-2 Framing Guns
• 1-2 Roofing Guns
• 3-5 Trim/Finish Guns

Super Quiet!
Only 8 Amps



Model JC10

Direct Drive - Oilless

- **1 HP** 1725 RPM, Auto Reset
- **2.35 CFM** Delivered at **90 PSI**, **5.3** Displaced

**Runs Approximately*
• 1-2 Roofing Guns
• 2-3 Trim/Finish Guns



Model VT25BIG

Direct Drive - Splash Lubricated

- **2.5 HP** 3400 RPM, Manual Reset
- **6.5 CFM** Delivered at **90 PSI**, **9.3** Displaced

**Runs Approximately*
• 2-3 Framing Guns
• 3-4 Roofing Guns
• 6-8 Trim/Finish Guns



Model FC2002

Direct Drive - Splash Lubricated

- **2 HP** 3400 RPM, Manual Reset
- **4.1 CFM** Delivered at **90 PSI**, **8.7** Displaced

**Runs Approximately*
• 1-2 Framing Guns
• 1-2 Roofing Guns
• 3-5 Trim/Finish Guns

Large
24 Gallon
Dolly Tank



Model FC250090L

Direct Drive - Splash Lubricated

- **2 HP** 3400 RPM, Manual Reset
- **5.1 CFM** Delivered at **90 PSI**, **10.1** Displaced

**Runs Approximately*
• 1-2 Framing Guns
• 2-3 Roofing Guns
• 4-6 Trim/Finish Guns



Model D2002HPV5

Direct Drive - Splash Lubricated

- **2 HP** 3400 RPM, Manual Reset
- **4.1 CFM** Delivered at **90 PSI**, **8.7** Displaced

**Runs Approximately*
• 1-2 Framing Guns • 1-2 Roofing Guns
• 3-5 Trim/Finish Guns



Model GD4000PV5H

Gas Direct Drive

- **118 cc (GX120)** Honda Engine, Splash Lubricated
- **4.6 CFM** Delivered at **90 PSI**, **8.3** Displaced

**Runs Approximately*
• 1-2 Framing Guns
• 2-3 Roofing Guns
• 4-6 Trim/Finish Guns

***Number of tools is dependent on the efficiency of the contractor's pneumatic system.**

ROLAIR[®] COMPRESSORS

S Y S T E M S

606 South Lake Street > P.O.Box 346 > Hustisford, WI 53034-0346 > **920.349.3281** > fax 920.349.3691 > www.rolair.com




Model 5715K17

I-Stage - Splash Lubricated

- 1.5 Motor w/Manual Reset
- 7.3 CFM Delivered at **90 PSI, 10.1** Displaced

*Runs Approximately

- 3-4 Framing/Sheathing Guns
- 3-5 Roofing Guns
- 7-9 Trim/Finish Guns



Model 4090HK17

I-Stage - Splash Lubricated

- 163 cc (GX160) Honda Engine w/Low Oil Shutdown, Auto Idle Down
- 9.3 CFM Delivered at **90 PSI, 13.1** Displaced

*Runs Approximately

- 3-5 Framing/Sheathing Guns
- 4-7 Roofing Guns




Model 6820K17

I-Stage - Splash Lubricated

- 2 HP - 110/220V Motor w/Manual Reset
- 8.8 CFM Delivered at **90 PSI, 12.5** Displaced

*Runs Approximately

- 3-5 Framing/Sheathing Guns
- 4-6 Roofing Guns
- 7-10 Trim/Finish Guns



Model 6590HK18

I-Stage - Splash Lubricated

- 196 cc (GX200) Honda Engine w/Low Oil Shutdown, Auto Idle Down
- 13.8 CFM Delivered at **90 PSI, 17.9** Displaced

*Runs Approximately

- 5-7 Framing/Sheathing Guns
- 6-9 Roofing Guns



Model 3230K24CS

II-Stage - Splash Lubricated

- 3 HP - 220V Motor w/Manual Reset
- 12.7 CFM Delivered at **90 PSI, 18.4** Displaced

*Runs Approximately

- 5-7 Framing/Sheathing Guns
- 6-8 Roofing Guns



Model 7722HK28

II-Stage - Splash Lubricated

- 270 cc (GX270) Honda Engine w/Low Oil Shutdown, Auto Idle Down
- 17.0 CFM Delivered at **90 PSI, 20.3** Displaced

*Runs Approximately

- 6-8 Framing/Sheathing Guns
- 8-10 Roofing Guns



Model 5230K30CS

II-Stage - Splash Lubricated

- 5 HP - 220V Motor w/Manual Reset
- 18.8 CFM Delivered at **90 PSI, 23.1** Displaced

*Runs Approximately

- 6-9 Framing/Sheathing Guns
- 7-11 Roofing Guns



Model 8422HK30

II-Stage - Splash Lubricated

- 270 cc (GX270) Honda Engine w/Low Oil Shutdown, Auto Idle Down
- 20.1 CFM Delivered at **90 PSI, 24.4** Displaced

*Runs Approximately

- 7-10 Framing/Sheathing Guns
- 9-12 Roofing Guns

***Number of tools is dependent on the efficiency of the contractor's pneumatic system.**